

## **064000 ARCHITECTURAL WOODWORK**

1. Cabinet Work: Materials and fabrication shall conform to Architectural Woodwork Institute specifications for Custom quality work as a minimum.
2. Cabinet hardware shall be furnished and installed by the installer of cabinetry. Cabinet hardware shall meet accessibility requirements. All cabinets in a room shall be keyed alike unless noted otherwise.
3. Plastic laminates: Before specifying, give due consideration to the particular condition of usage that will be encountered. Of special concern are flame spread, chemical resistance, fuel contribution, smoke generation and toxicity for plastic laminates and for the adhesives used to install them. Avoid use of plastic laminates in residence halls. Do not specify plastic laminate in wet environments or for use on window sills.
4. Solid Surfacing Material: Shall be utilized in all wet locations, with a molded lavatory, and for windowsills. It is preferred in other non-wet locations where budget permits.
5. Prior to delivery of materials on site for installation, the Contractor shall provide the proper environmental controls for material storage (i.e. weatherproofing, climate control). These controls shall be maintained for the duration of the project.